## **SCHEDULE OF PRICES**

**FOR** 

## **TOWN OF DRUMHELLER**

STIRLING DITCH & 2<sup>ND</sup> AVE TENDER NO. 2023-031





Kerr Wood Leidal Project No: 3446.012

**MAY 2023** 

#### SCHEDULE OF PRICES

#### **1.1** *TERMS*

- .1 For each price specified in the Schedule of Prices, include all costs and charges required to perform the Work including overhead charges and profit, and all costs of all relatedWork for which payment is not specified elsewhere.
- .2 Subject to the provisions of the Contract Documents, the total amount of the Schedule of Prices shall cover all of the Contractor's obligations under the Contract and all matters and things necessary for performance of the Work in accordance with the Contract Documents.
- .3 Payment will be made only for items specified in the Schedule of Prices. Costs and charges not directly provided for in the Schedule of Prices will be deemed to be included therein.
- .4 Estimate the cost for Mobilization and Demobilization and Contract Management as two items. One for the work to be completed in 2023 and one for the work to be completed in 2024.
- .5 All costs associated with the implementation of Dutch elm disease / European elm bark beetle / native elm bark beetle control measures will be considered incidental to the Work and no separate or additional payment will be made. Payment upon submission of landfill waybills to the Town by the Contractor.
- .6 All costs associated with the implementation of black knot fungus control measures will be considered incidental to the Work and no separate or additional payment will be made. Payment upon submission of landfill waybills to the Town by the Contractor.
- .7 Work or material included in any one item will not also be measured for payment under another item. No item will be paid for more than once.
- .8 Omissions or errors in any item including quantities in the Schedule of Prices will not invalidate the Contract nor release the Contractor from any of his obligations or liabilities under the Contract.

### 1.2 LUMP SUM ITEMS

- .1 Breakdown of Lump Sum Items
  - .1 If requested, submit to the Town a breakdown of each Lump Sum item included in the Schedule of Prices, within 2 days after the commencement date of the Contract.
  - .2 Provide sufficient details as may be required by the Town to identify the principal

components of the Work and to permit ready valuation of Work performed.

# Schedule A – Stirling Ditch & 2<sup>nd</sup> Ave

**TOWN OF DRUMHELLER** 

FOR Town of Drumheller Tender No.: 2023-031

**KERR WOOD LEIDAL PROJECT NO.: 3446.012** 

ITEM NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE	TOTAL BID
		1. Stirling Ditch & 2nd A	Ave	
1.1	Mobilization (including demobilization and submittals)	1	\$ N/A	\$ N/A
1.2	Remove and Salvage Traffic Sign	1	\$	\$
1.3	Remove and Dispose Fence	23 m	\$	\$
1.4	Remove and Dispose Culvert (<700mm)	8 m	\$	\$
1.5	Common Excavation (including placement and compaction)	1,600 m³	\$	\$
1.6	Common Excavation and Dispose Offsite	100 m³	\$	\$
1.7	Import Fill Material (including placement and compaction)	20 m³	\$	\$
1.8	Topsoil Placement	3,060 m²	\$	\$
1.9	Supply and Install Class 1M Riprap	85 m³	\$	\$
1.10	Supply and Install Culvert 300 mm	14 m	\$	\$
1.11	Supply and Install Culvert 600 mm	12 m	\$	\$
1.12	Supply and Install Granular Filter	56 m³	\$	\$
1.13	Supply and Install 6-80 Gravel	175 m³	\$	\$
1.14	Supply and Install 4-20 Gravel	285 m³	\$	\$
1.15	Supply and Install Red Shale Gravel (OPTIONAL)	20 m³	\$	\$
<del>1.16</del>	Supply and Install Class A Fence (including gate)	<del>23 m</del>	\$ N/A	\$ N/A
1.17	Topsoil Stripping	612 m³	\$	\$
1.18	Hydroseeding/Hydromulching	3,060 m²	\$	\$
1.19	Tree & Brush Clearing	1,350 m <sup>2</sup>	\$	\$

ITEM NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE	TOTAL BID
1.20	Supply and Install Non-Woven Geotextile	240 m²	\$	\$
1.21	Supply and Install GEOCOIR	3,060 m <sup>2</sup>	\$	\$
1.22	Water Valve Extension	1	\$	\$
1.23	Sanitary Cleanout Protection	1	\$	\$
1.24	Shed Removal	1	\$	\$
1.25	Prepare Subgrade Surface	1,930 m²	\$	\$
1.26	Remove and Dispose Concrete Sidewalk	140 m	\$	\$
1.27	Supply and Install Concrete Sidewalk	151 m	\$	\$
1.28	Supply and Install RAP Asphalt	755 m²	\$	\$
1.29	Remove and Re-Install 724 Hunter Dr Address Post	1	\$	\$
1.30	Remove and Re-Install 500 mm CSP Culvert	15 m	\$	\$
1.31	2023 Mobilization (including demobilization and submittals)	1	\$	\$
1.32	2024 Mobilization (including demobilization and submittals)	1	\$	\$
TOTAL BID AMOUNT:				

# **Summary Sheet**

## TOWN OF DRUMHELLER

# FOR Town of Drumheller Tender No.: 2023-031 – Stirling Ditch & 2<sup>nd</sup> Ave

**KERR WOOD LEIDAL PROJECT NO.: 3446.012** 

ITEM NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE	TOTAL BID
2. SUMMARY SHEET				
2.1	Schedule A – Stirling Ditch & 2 <sup>nd</sup> Ave	1	\$	\$
2.2	Contingency	1	15%	\$
TOTAL BID AMOUNT:				

Contractor's Representative Signature	Contractor's Name (Print)
·	
	_
Print Name	
Position in Company	Witness or Seal
Contractor's G.S.T. No.	Date

Position in Company

Date

Email.: purchasing@drumheller.ca

### **TENDER AMENDMENT FORM**

### **TENDER AMENDMENT**

Town of Drumheller – Stirling Ditch & 2<sup>nd</sup> Ave Town of Drumheller Tender No.: 2023-031

Schedu	le A				
We,					
	(Name of Contractor)				
the und table.	ersigned, modify the Tender Unit Pri	ice Schedule foi	r our Tender as shov	vn in the following	
CONTRACT UNIT PRICE SCHEDULE CHANGES Replacing ALL Previous Unit Price Changes					
BID ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE CHANGE + OR -	TOTAL CHANGE FOR THIS ITEM + OR -	
+ or – Change in Total Tender					
We also	acknowledge and agree that:				
2. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3. 3.	submitted changes are all null and void.  2. We accept full responsibility for any lack of confidentiality arising from the use of this process.				
	Being				

Subject: Stirling Ditch & 2<sup>nd</sup> Ave – Schedule A

Signature

Company Name

Kelcie Wilson, C.E.T., Capital Project Manager

Of

Email To:

Town of Drumheller 2023-031 Kerr Wood Leidal Associates Ltd.

dated